

- PCV electrical conduit (min. Ø60) for electrical connections between dock leveler and control panel.
- 4. Bay for car lift.

- 1. Dock leveller must be installed before pouring concrete floor.
- 2. PCV electrical conduit (3) must be placed as well before flooring.
- At bumper fixation points forces of 59kN to be expected on prefabricated concrete with 30tons lorries and a velocity of 5km/h.

NW	- nominal width		2000	2000	2000	2250	2250	2250	
NL	- nominal length		2000	2500	3000	2000	2500	3000	
NW + 60	- foundation width		2060	2060	2060	2310	2310	2310	
Н	- construction height			710	710	710	710	710	
A1	- additional rebar spacing		-	550	550	-	550	550	
A2	- additional rebar spacing		-	-	500	-	-	500	
Designed by	Checked by	Approved by	D	ate					
P. Pomykała	M. Palega	G. Mazurkiewicz			X : X		26.10.2021		A3



Guidelines for spacing between rebars

Edition Sheet AMTRV-PRO-RS 1.2 1 / 1

^{*} The drawing is an illustrative drawing, not made to scale. Detailed technical solutions may differ from the ones shown in the drawing.